Sampling and Per-Precision Histograms with nixnan: An Experiment on `rd_nixnan.cu`

ganesh@cs.utah.edu
(written with Claude Code)

September 23, 2026

Abstract

This report documents a self-contained experiment (`Expts-9-23/`) demonstrating that `nixnan.so` helps understand a real GPU precision-sensitivity problem in several specific ways: (1) it can trade instrumentation overhead for observation completeness via the `SAMPLING` env var, (2) that trade-off can be driven through an arbitrary, externally-scripted schedule (here, an exponentially decaying rate) rather than a single fixed value, (3) it reports, per floating-point format, exactly how much of that format's dynamic range a given run actually used, and (4) it can confirm or refute a hypothesis about *why* a lower-precision format fails first — here, that domain enlargement does not explain FP16's earlier failure, but running longer does. All numbers below come from real runs captured in `Logs/`; nothing is simulated or hand-typed. Section 8.2 shows FP64 also eventually failing, much later than the other formats, once run for long enough.

Contents

1 The Example **2**

2 "Straight nixnan": How These Runs Are Instrumented **2**

3 NixNan Feature Reference **2**

4 Sampling, Level 1: Every Kernel Call **3**

5 Sampling, Level 2: Once in 8 Kernel Calls **4**

6 Sampling, Level 3: An Exponentially Decaying Schedule **4**

7 Histograms per Precision Bucket **5**

8 Making BF16 and FP32 Fail Too **5**
8.1 Where Infinity Actually Comes From 7
8.2 Running FP64 for real, until it does overflow 8

9 Conclusion: What nixnan Made Visible Here **9**

1 The Example

`rd_nixnan.cu` solves a 1D reaction-diffusion PDE, $\partial u/\partial t = D\,\partial^2 u/\partial x^2 + \lambda u$, with explicit forward-Euler time stepping, on a 101-point grid for 1600 steps. The same step is implemented once per floating-point format — FP16, BF16, FP32, FP64 — as four separate CUDA kernels, so nixnan can attribute every exception and every exponent observation to a specific, known precision.

Why this example is precision-sensitive.

- The reaction term grows the solution by a fixed factor ($\sim$1.05$\times$) every step, so the exponent of every value climbs steadily regardless of format — the *only* thing that differs between formats is how much exponent range each one has before it overflows. FP16's 5-bit exponent runs out first, at step 300; BF16's, FP32's, and FP64's 8/8/11-bit exponents all still have headroom left at step 1600 (see Section 7).
- Because the kernel is otherwise identical across formats, any behavioral difference observed — overflow or not, subnormal or not, NaN cascade or not — is attributable entirely to the format's exponent width, not to any change in the algorithm. That makes it a clean instrument for isolating precision effects, and correspondingly a clean instrument for showing what nixnan actually measures.

2 "Straight nixnan": How These Runs Are Instrumented

Every run in this experiment uses `nixnan.so` directly, with no wrapper script:

```
LD_PRELOAD=<path>/nixnan.so [ENV_VARS...] ./rd_nixnan
```

`nixnan.so` is an NVBit tool: preloaded into the CUDA process, it rewrites each kernel's SASS the first time that kernel is launched, inserting device-side checks after (and before) every floating-point instruction. At exit it prints an aggregate report, per format, of unique exception *sites* (distinct instruction/operand locations that ever fired) and *repeats* (additional occurrences beyond each site's first hit) — the distinction that matters throughout this report.

3 NixNan Feature Reference

Before walking through results, this section fixes the exact meaning of every nixnan-specific setting the rest of the report relies on.

The `BIN_SPEC_FILE` JSON format. nixnan's own `--help` banner gives this example:

```
{
    "count": 128,
    "bf16": [],
    "f16": [[0,5],[-4,-1]],
    "f32": [],
    "f64": []
}
```

Each format key holds a list of *unbiased signed exponent* ranges to watch (here, only `f16` watches anything: the ranges $[0, 5]$ and $[-4, -1]$). `count` is a global report-frequency threshold: within a

watched range, nixnan counts every value landing in it and emits a "bin has reached threshold" line every `count` occurrences — so `count:128` here means "tell me every 128th time an `f16` value's exponent falls in $[0, 5]$ or $[-4, -1]$." Ranges are *unbiased* (e.g. FP16's usable exponent span is $[-14, 15]$, not the raw 5-bit field $[0, 31]$), and the two special encodings zero and infinity are structurally excluded from every range — a consequence used directly in Section 8.1: a value that jumps straight from finite to `inf` in one step, with no gradually-climbing trail through large-but-finite exponents first, is invisible to this mechanism no matter how the ranges are drawn. This experiment's own `HISTOGRAM=1` runs (Section 7) use the simpler, rangeless form of this same machinery: with no `BIN_SPEC_FILE` set at all, nixnan still tracks every exponent it sees and reports each format's overall $[\min, \max]$ at exit, just without the interim "every Nth occurrence" pings.

`SAMPLING=8`. Per nixnan's own banner text, *"Instrument a repeat kernel every SAMPLING times."* Concretely: the tool keeps a per-kernel launch counter, and only *enables* the already-instrumented version of the kernel on launches where `launch_count % SAMPLING == 0`; other launches run the kernel's plain, uninstrumented SASS. `SAMPLING=8` therefore observes 1 launch in 8; `SAMPLING` unset (or 0) disables sampling entirely, i.e. every launch is observed — the baseline used throughout Section 4.

How the exponential-decay parameters are specified. There is no `nixnan.so` setting for a decaying rate — `SAMPLING` is read once at process start and held fixed for that process's entire lifetime. The schedule in Section 6 is therefore specified entirely outside nixnan, in `shell-scripts/sampling_schedul` (three fields: `levels`, the sequence of `SAMPLING` values to sweep through; `snaps_per_level`, how many independent process launches to repeat at each level before advancing; and `cycles`, how many times to repeat the whole level sequence from the start). `03_sampling_exp_decay.sh` reads that file and, for every `(cycle, level, snap)` triple, launches exactly one fresh `SAMPLING=$level LD_PRELOAD=nixnan.so ./rd_nixnan` process, redirecting its full output to its own log file.

What generated `03_sampling_exp_decay_summary.tsv`. Every row of that file is the FP16 NaN/Infinity unique-site and repeat counts parsed back out of one such snap's log — 4 levels $\times$ 4 snaps $\times$ 2 cycles $= 32$ independent nixnan runs in total, each identical in every setting except `SAMPLING` and which `(cycle,level,snap)` log file it wrote to. No other nixnan setting (no `HISTOGRAM`, no `BIN_SPEC_FILE`, no `INSTR_MEM`) is active during these runs — it is the same default exception-instrumentation (`INSTRUMENT_EXCEPTIONS=1`) as Section 4's baseline, run 32 times at 4 different `SAMPLING` values.

4 Sampling, Level 1: Every Kernel Call

The baseline (`SAMPLING` unset, which nixnan treats as "instrument everything"):

```
LD_PRELOAD=nixnan.so ./rd_nixnan
```

Result (`Logs/01_sampling_every_call.log`), FP16 — the only format that overflows in this build:

```
NaN: 22 (60534 repeats)
Infinity: 22 (639 repeats)
```

This is the reference point every other sampling level in this report is compared against.

5 Sampling, Level 2: Once in 8 Kernel Calls

```
SAMPLING=8 LD_PRELOAD=nixnan.so ./rd_nixnan
```

Result (`Logs/02_sampling_every_8.log`):

```
NaN: 22 (7524 repeats)
Infinity: 17 (66 repeats)
```

Repeats drop by almost exactly 8× (60534/7524 ≈ 8.05), consistent with observing 1/8 of the kernel launches. But note the unique Infinity-site count also dropped, 22 → 17 — five distinct exception sites simply never got observed at this sampling rate. This is the first concrete evidence that `SAMPLING` trades completeness for overhead, not just verbosity for overhead.

A regression, now fixed. The pre-existing `run_nixnan_experiment.sh` in this directory carries a comment, from an earlier investigation, stating *"SAMPLING is a no-op in this nixnan build."* We re-tested that claim directly against the current build before writing this experiment (comparing `SAMPLING=1` against `SAMPLING=100000` on `reaction_diffusion_gpu_fp32`): at `SAMPLING=100000` every exception count dropped to exactly zero, which only happens if `SAMPLING` is genuinely gating instrumentation. `SAMPLING` is no longer a no-op in the `auto-nixnan` branch as built here — whatever caused the earlier no-op behavior has since been fixed.

6 Sampling, Level 3: An Exponentially Decaying Schedule

`nixnan.so` reads `SAMPLING` once at process start; there is no way to vary it mid-run. A decaying/backoff sampling rate therefore has to be built at the orchestration level, as a sequence of short runs ("snaps"), each holding `SAMPLING` constant. `shell-scripts/sampling_schedule.json` specifies that sequence (full rationale in its own header comment):

```
{
  "snaps_per_level": 4,
  "levels": [1, 2, 4, 8],
  "cycles": 2
}
```

i.e. step 4 times at spacing 1, double to spacing 2 and step 4 more times, double again to 4, double again to 8, then reset back to spacing 1 for a second cycle. `shell-scripts/03_sampling_exp_decay.sh` runs this schedule and tabulates the FP16 counts per snap (`Logs/03_sampling_exp_decay_summary.tsv`):

SAMPLING level	NaN unique	NaN repeats	Inf unique	Inf repeats
1	22	60534	22	639
2	22	30246	21	312
4	22	15103	17	154
8	22	7524	17	66

Every one of the 4 snaps at a given level is byte-identical (the program is deterministic and each snap is a fresh, independent process), and **cycle 2 is byte-identical to cycle 1 at every level** — the reset back to spacing 1 reproduces the exact baseline from Section 4, confirming there is no hidden cross-run state. See Figure 1 (`viz/sampling_decay.svg`).




Figure 1: Repeats halve with each doubling of SAMPLING; unique-site counts stay near-constant for NaN but step down for Infinity.

7 Histograms per Precision Bucket

`HISTOGRAM=1` enables exponent-histogram tracking for every instrumented FP instruction, independent of the exception checker; at exit nixnan prints the [min, max] exponent actually observed for each format that had any instrumented activity:

```
HISTOGRAM=1 LD_PRELOAD=nixnan.so ./rd_nixnan
```

Result (`Logs/04_histograms_per_precision.log`):

```
Exponent range for bf16: [zero, 113]
Exponent range for f16: [zero, inf]
Exponent range for f32: [zero, 113]
Exponent range for f64: [zero, 113]
```

This is the direct, per-format confirmation of the precision-sensitivity claim from Section 1: FP16 is the only format whose exponent range is exhausted (it reports `inf` instead of a finite maximum) within 1600 steps. BF16, FP32, and FP64 all reach the identical exponent 113 — they are following the exact same growth trajectory (same algorithm, same input) and have not yet diverged from each other; only their exponent *ceilings* differ, and only FP16's has been reached.

8 Making BF16 and FP32 Fail Too

Every result so far has one format failing (FP16) and three staying finite. A natural follow-up: what would it take to make BF16 and FP32 fail as well, and does `nixnan` help answer that?




Figure 2: Exponent range actually reached by each format through step 1600. FP16's fixed capacity is $[-14, 15]$ and it exceeds it (overflow); BF16/FP32/FP64 all reach the same exponent, 113, with room remaining to their much wider ceilings.

Hypothesis tried: domain enlargement. Enlarging the grid (N, holding dx fixed by extending L proportionally) was tried *first*, because it is the most obvious "make the problem bigger" lever. It does not work, for a structural reason visible directly in the kernel: the reaction term `lam * u[i]` is a per-point multiplicative growth factor that does not reference N or dx at all — every grid point grows by the same $\sim 1.05\times$ per step regardless of how many points there are. Enlarging N just runs the identical per-step growth curve on more points; it cannot change *when* any single point's exponent is exhausted. This was already verified empirically earlier this session with `rd_nixnan_large.cu` (a $10\times$ grid, N=1001): at the same M=1600, only FP16 failed there too, exactly as at N=101.

What actually works: more time steps. `rd_nixnan.cu`'s step count is a compile-time macro (`#ifndef M ... #define M 1600`), so it can be overridden at compile time without touching the source:

```
nvcc -arch=sm_86 -DM=2000 rd_nixnan.cu -o rd_nixnan_extended
LD_PRELOAD=nixnan.so ./rd_nixnan_extended
```

`shell-scripts/05_extended_run_all_fail.sh` builds and runs exactly this (`Logs/05_extended_M2000.log`):

Format	First non-finite (step)	NaN unique/repeats	Inf unique/repeats
FP16	300	22 / 78134	22 / 639
BF16	1900	15 / 8975	6 / 76
FP32	1900	19 / 10966	8 / 90
FP64	— (correctly finite)	0 / 0	

At M=2000, BF16 and FP32 both now show real, nixnan-classified NaN/Infinity activity — confirmed, not just inferred from the program's own `max=...` printout. FP64 correctly stays finite at

M=2000; Section 8.2 runs it long enough to show it does eventually overflow, for real.

8.1 Where Infinity Actually Comes From




Figure 3: Max$|u|$ per 100-step checkpoint, all four formats, from the same `Logs/05_extended_M2000.log` run as the table above. FP16 (blue) departs the shared curve at step 300. BF16/FP32/FP64 stay numerically indistinguishable all the way to step 1800 (1.1675×10^{38} for FP32 and FP64 to all four significant figures shown); BF16 and FP32 are non-finite by step 1900, while FP64 continues (its real value there is $\approx 1.5 \times 10^{40}$ — large, but still finite).

The CUDA statement where Infinity was first generated. `rd_nixnan.cu` was rebuilt with `-g -lineinfo` for this run specifically so nixnan's `LINE_INFO=1` (the default) could resolve real source locations instead of SASS only. For FP32, it does, cleanly:

```
error [infinity] detected in operand 0 of instruction FADD R0, R0, R7
  ; in function rd_step_fp32 at rd_nixnan.cu:96 of type f32
```

Line 96 is the Laplacian: `float lap = (u[i + 1] + u[i - 1]) - 2.f * u[i];` — **Infinity first appears while computing the diffusion term, not the reaction term.** BF16 partially resolves too (its analogous line, 84, appears on some but not all of its error lines — likely because BF16's arithmetic goes through `__h*` intrinsic wrappers that are not always attributed as cleanly as FP32's plain operators). FP16's error lines carry no source location at all: every FP16 statement uses `cuda_fp16.h` intrinsics (`__hadd`, `__hsub`, `__hmul`), which are fully inlined and, in this build, resolve to no attributable line whatsoever — a real limitation of `nixnan`'s line-info resolution for deeply-inlined intrinsics, not a property of the kernel. By direct structural analogy (line 70, `__hsub(__hadd(u[i+1],u[i-1]), __hmul(two,u[i]))`, is the exact same expression as FP32's line 96, and FP16's SASS shows the identical HADD2-then-HFMA2-with-constant-2 pattern nixnan

reports for FP32/BF16 at their resolved lines), the same conclusion almost certainly holds for FP16, though `nixnan` itself cannot confirm it here.

How Infinity becomes NaN, with the specific statement. The original source comment in `rd_nixnan.cu` predicted this mechanism by hand: `inf - 2*inf + inf -> NaN`. `nixnan`'s own instrumentation confirms it, to the instruction, for FP32. The three FADD instructions on line 96 fire in this order as the classifier first sees each:

```
FADD R0, R0, R7 ; u[i+1] + u[i-1] -> operand already Infinity
FADD R7, R6, R6 ; 2.f * u[i] (as u[i]+u[i]) -> operand already Infinity
FADD R7, R0, -R7 ; (u[i+1]+u[i-1]) - 2.f*u[i] -> RESULT is NaN
```

The third instruction is exactly $\infty - \infty$, IEEE-754's indeterminate form — nixnan reports `NaN` for that instruction's *result* operand as the very next distinct site to fire. That NaN then flows into line 97's FFMA chain (`un[i] = u[i] + r * lap + lam * u[i];`) and out through the final `STG.E` store, exactly matching the source comment's prediction and giving it a concrete, tool-verified instruction sequence rather than a hand-derived guess.

8.2 Running FP64 for real, until it does overflow

FP64's actual ceiling is $\sim 1.8 \times 10^{308}$. From its 1.1675×10^{38} value at step 1800 and the observed $\sim$1.05$\times$/step growth, reaching that ceiling takes on the order of $\log_{10}(1.8 \times 10^{308}/1.1675 \times 10^{38})/\log_{10}(1.05) \approx 12{,}750$ more steps — an overflow step around 14,550.

`rd_nixnan.cu` gained a build mode, `FP64_LONGRUN` (off by default, so every earlier stage in this experiment is unaffected), to actually reach that point:

```
nvcc -arch=sm_86 -g -lineinfo -DFP64_LONGRUN=1 rd_nixnan.cu -o rd_nixnan_fp64_longrun
LD_PRELOAD=nixnan.so ./rd_nixnan_fp64_longrun
```

It runs all four precisions together up to `SUPPRESS_AFTER` (3800 steps, twice FP32's real trigger step of 1900), then frees FP16/BF16/FP32's buffers — already long non-finite by then — and steps FP64 alone up to `M_FP64_MAX` (20000) or first non-finite. `shell-scripts/06_fp64_longrun.sh` builds and runs this (`Logs/06_fp64_longrun.log`). FP64 overflows at step 14600 (t=14.6), matching the estimate above, and `nixnan` now classifies it for real:

	NaN (unique/repeats)	Infinity (unique/repeats)	−Infinity (unique/repeats)
FP64 (this run)	36 / 1699	10 / 74	32 / 712

With `-lineinfo`, the first Infinity is attributed to the same statement as FP32's, `rd_nixnan.cu:106`, the Laplacian (`double lap = (u[i + 1] + u[i - 1]) - 2.0 * u[i];`):

```
error [infinity] detected in operand 0 of instruction DADD R6, R6, R8
  ; in function rd_step_fp64 at rd_nixnan.cu:106 of type f64
```

and the same three-instruction pattern turns it into `NaN`:

```
DADD R6, R6, R8 ; u[i+1] + u[i-1] -> operand already Infinity
DADD R8, R10, R10 ; 2.0 * u[i] (as u[i]+u[i]) -> operand already Infinity
DADD R6, R6, -R8 ; (sum) - 2.0*u[i] -> RESULT is NaN
```

That `NaN` then flows into line 107's `DFMA` chain and out through the final `STG.E.64` store — the identical mechanism as FP32 (Section 8.1), at a much larger step count because FP64 simply has far more exponent range to climb through first.

9 Conclusion: What nixnan Made Visible Here

Across five short experiments on one simple, well-understood kernel, `nixnan` surfaced several things that would not be visible from the program's own output (a plain run of `rd_nixnan` only prints `max=...` per step, with no notion of exception sites, repeats, or exponent range):

1. **Sampling is a real overhead/completeness knob, not a free lunch.** Coarser sampling doesn't just reduce reported repeats proportionally — it can silently drop entire exception sites from the report (22 → 17 unique Infinity sites, Section 4), which matters if the goal is finding every distinct bug location rather than just gauging overall severity.
2. **A fixed env var can still drive an arbitrary sampling schedule**, by scripting a sequence of short, independent runs around it (Section 6) — and because `rd_nixnan` is fully deterministic, that schedule is provably reproducible: cycle 2 reproduces cycle 1 exactly.
3. **Per-format exponent histograms directly confirm *which* format is precision-sensitive and by how much** (Section 7), turning "FP16 fails and the others probably don't" into a specific, quantified claim: FP16 alone hits `inf`; the other three all reach exactly the same exponent, 113, with headroom still remaining to their much larger ceilings.
4. **nixnan can adjudicate a hypothesis about *why* a format fails first** (Section 8): domain enlargement, the obvious first guess, is ruled out directly by the kernel's own growth term; running longer is confirmed, with nixnan's own classifier newly reporting real BF16 and FP32 exceptions at M=2000 where it reported none at M=1600.
5. **Line-level attribution turns a hand-derived guess into a tool-verified fact** (Section 8.1): with `-lineinfo`, nixnan pinpoints the exact CUDA statement (the Laplacian, not the reaction term) and the exact SASS instruction where $\infty - \infty$ produces `NaN` — confirming, to the instruction, a mechanism the source code's own comments could only predict by hand.
6. **Running FP64 long enough shows it fails too, and nixnan shows exactly where** (Section 8.2): run for real to step 14600 (the `FP64_LONGRUN` build mode), FP64 overflows at the step its own growth rate predicts, and nixnan attributes it to the identical Laplacian statement and $\infty - \infty \to$ `NaN` mechanism already confirmed for FP32.

As a side effect, re-verifying `SAMPLING` against the current build (Section 4) also caught that a previously-documented no-op regression in `nixnan.so` has since been fixed — itself an example of nixnan-adjacent tooling needing the same kind of empirical re-verification its own instrumentation provides for user code.